



NOvA Accelerator Upgrades: Status

Phil Adamson
Fermilab
pa@fnal.gov



“It’s all fairly
straightforward”
-- Jeff Hartnell
this morning



About this talk




- This talk is not about the wonderful physics programme offered by the NOvA beamline
 - NOvA
 - MINERvA
 - MINOS+
 - See plenary talk by Jeff Hartnell this morning
- Brief overview of current accelerator complex
- Major upgrades required for NOvA
- Status & schedule
- This talk does not contain every detail of the upgrade project
 - Please feel free to ask about your favourite subject



Current NuMI operation

%


Linac: 750 keV – 400 MeV
Booster: 400 MeV – 8 GeV
Main Injector: 8 GeV – 120 GeV
Slip-stack 11 booster batches
2 batches to antiproton
9 batches to NuMI






NuMI neutrino beam

%



- Neutrino energy tuned by moving target (usually LE)
- Change horn polarity to select $\bar{\nu}_\mu$ or ν_μ





NOvA upgrades

%



- Increase NuMI primary proton beam power
 - 330 (380) kW -> 700 kW
- Additional focus on loss control
 - Double the beam power
 - Same tunnels
- Change neutrino beam energy (focussing)
 - Optimize flux at off-axis NOvA location






Increasing beam power

%



Recycler



Main Injector

- Move slip-stacking to recycler
- 11 batch -> 12 batch
- Increase Main Injector ramp rate (204 GeV/s -> 240 GeV/s)
- 330 (380) -> 700kW with only ~10% increase in per-pulse intensity



So need to rebuild recycler



- Remove:
 - Old transfer lines
 - Small aperture (pbar: $6\pi/2\pi$, protons: $15-20\pi$)
 - Stochastic cooling
 - Electron cooling
 - Pelletron
 - Rebuild MI-30 with FODO lattice
 - Various odds and ends that might be aperture restrictions
- Add:
 - New injection line from MI8 to recycler
 - New RR->MI transfer line
 - 53 MHz RF system for slip-stacking
 - Instrumentation
 - BPMs
 - Low-mass Ti multiwires
 - IPMs
 - Must maintain vacuum at $10^{-10} - 10^{-11}$ torr (TSPs)



New MI-8 line

%

- Switched dipole at 849
 - ADCW (wide-gap modification of old ADC magnet)
- Strontium Ferrite permanent magnet dipoles like rest of MI-8
- Two Samarium Cobalt dipoles (space constraints)
- Strontium Ferrite recycler quads, powered quad trims for lattice matching



- 1-week shutdown in March 2011
 - Electric company replacing switchgear offsite
- Installed first PDD magnet in new MI8



Rebuild 30 straight

%



- New permanent quads for 30 straight in recycler
 - Total cost cheaper than re-making existing quads
 - ALARA



53 MHz RF in Recycler



- Build 3 RF cavities
 - A, B and hot spare
 - 150 kV per cavity
 - Operating range:
 $52.809 \text{ MHz} \pm 1260 \text{ Hz}$
 - 10 KHz fast ($\sim 40 \mu\text{s}$) phase shifters from Proton Driver
- Recycle PAs and modulators from Tevatron
- LLRF close to a copy of MI system






11 batches -> 12 batches



%

- Currently place 81 bunches every 86 in MI
- For NOvA, place 81 bunches every 84 in Recycler. ($84 = 588/7$)
- Faster rising/falling edges -> many short kickers (6)
- Already have 7 RKA magnets in MI: Gap Clearing Kicker system for loss control







Gap Clearing Kicker System



6/7 magnets will move up to recycler for NOvA




GCK measurements



- Edges within specification
- Slower edge in damper measurement might be artifact


- For recycler, building “tail bumper” to cancel tail
- Tail measurement similar to electrical measurements (good)





GCK reducing local losses

%






Increase MI ramp rate

%

- 2 new MI cavities to maintain bucket area
- New transformer for vertical quad bus
- Increased heat load on cooling ponds
 - Will need more cooling for summer – study underway looking at future cooling needs (not just NOvA)
 - More ponds?
 - Run a chiller in summer?
 - Shade ponds?





Beamline upgrades



- Increase rep rate
 - 2.2s (2.0s) -> 1.33s
- Replace 5 3Q120 quads with ones from A150 beamline (better cooling)
- Upgrade magnet power supplies
 - Faster ramp
 - BULB
 - Better regulation
 - Current monitor -> beam permit
- New kicker power supply
- Beam intensity doubled, but beam loss in water-bearing rock must not double
 - New 1 mil Ti multiwires - lower mass in beam




Off-axis neutrino beam



$$E_\nu = \frac{\left(1 - \frac{m_\mu^2}{m_{\pi,K}^2}\right) E_{\pi,K}}{1 + \gamma^2 \theta^2}$$


- Off-axis, neutrino energy driven by angle
- Adjust focusing to optimize flux





Target Hall Upgrades

%






NOvA target

%



- NuMI target (top) must fit inside horn 1
 - Small, mechanically weak. Recent problems – failure of water cooling lines
- NOvA target (right) upstream of horn 1 (neutrino energy from off-axis angle)
 - Much more robust design. Water cooling 8 times further away from beam than NuMI




- Target construction in progress – delivery this fall



Target Carrier



- “Prototype” carrier complete
 - Expect to use as first production carrier
 - Shown here with target/baffle mockup





Schedule & Summary



- Tevatron operation completes by October 1
- Begin NOvA shutdown March 5 2012
 - Shutdown scheduled for 11 months
 - Current installation schedule has work completed in 8-9 months
 - Then commission new accelerator complex
 - If accelerator work done before NuMI, can get an early start on commissioning
- NOvA accelerator upgrades proceed on schedule
- I look forward to commissioning the new complex and swift progress towards 700 kW



o/o

NOvA Accelerator Upgrades: Status

Phil Adamson

Fermilab


pa@fnal.gov



Slip-stacking

%


- Neutrino experiments want more beam!
- Inject 11 batches rather than 6
 - But pay for it with increased losses
 - (<95% efficiency)





Slip-stacking recapture (real data)

%





Transfer and new MI8 lines

