

# MERIT Installation at CERN


K. McDonald

For the MERIT Collaboration

April 13, 2007

# MERIT control room

- Located in building 272
  - 272 S-002
  - Equipped with 12 Ethernet ports (currently 4 PCs installed and 2 portable outlets)



- Communicates with the experimental setup in TT2/A ONLY via Ethernet (no hard wires).

# TT2A

- TT2A: Ready for goods reception.




# Magnet and Mercury System Arrive at CERN 16 May 2007



Stored in West Hall (Bldg 180/183)




# Cryo System Exercised in Bldg 180 via Control from Bldg 272



Test magnet with cryo system in Bldg 180 starting 10 April.

## HiPot Test of Magnet @ 800 V

- Measure resistance between different points (I/V measurement). Slight bending of the middle coil might cause leakage current.
- Equipment:
  - Power supply: Caen N470
    - Current monitor at  $\mu\text{A}$  accuracy
  - Current meter: Keithley 2001
    - Tens of nA



Contact points  
Coil #1  
Coil #2  
Coil #3  
"Shorting cable"

Each coil  $\sim 100 \text{ G}\Omega$ , magnet  $\sim 30 \text{ G}\Omega$  (and "shorting cable"  $\sim 400 \text{ M}\Omega$ ).

# Room-Temperature Pressure Test of Magnet to 12.5 Bar



"Antler" of pressure relief valves added.  
Cryostat held 12.5 bar of He gas for 1 hour.  
No leaks detected with sniffer.



Cryocomp valve operator removed from vacuum jacket for proper operation of the pressure relief valve.



# West Area power converter 8000A<sub>dc</sub>, 1000V<sub>dc</sub>

**Converter topology**


**18 kV cell**

**Power transformers  
(in an oil tank)**

**2x4  
Rectifier  
bridges**

**Passive  
LC filter**

**CROWBAR**



Connect midpoint of power supply to ground thru 1Ω, so magnet runs at ±350 V.




Mercury "Snout" Turnbuckles Worked Loose During Transport  $\Rightarrow$  Snout Fell 10 cm  
Rubber Collar Stretched by  $\sim 5$  cm.  
 $\hat{=}$  Damage to the Primary Containment?




Snout  
guy wires  
restored by  
M. Lazzaroni



# Check of Integrity of Fiberoptics using a Laser Pointer




All fibers OK, tho image from fibers 1 and 3 less bright than those from 2 and 4.



# Primary Containment Vessel Still Passes the 1-PSI Pressure Test




Removed rubber collar to inspect flexible Hg connectors. They still look good.




Hg Containment Schematic  
85112007

Top view



Side view



# Installation of MERIT Equipment in TT2/TT2A Tunnels ~ 1 May

