



MERcury Intense Target (MERIT) Experiment Layout

A.Fabich for CERN AB-ATB




The Experimental Layout



- Detailed ACAD drawings of the TT2 and TT2A tunnels are now available
 - Include all the shielding walls and services for nTOF already installed in the area
 - Used to define the passage of the cryogenics exhaust line into TT10 and the layout of the cable passage holes between TT2/TT2A tunnels
- A preliminary rack allocation of the experimental services in TT2 tunnel is included
 - Subject of discussion – a decision is needed before the first cables are ordered/installed.


General layout




The Experimental Layout

Cable passages

- Three holes will be drilled:
 - Upstream: OD=30cm for cryogenics
 - Middle: for optical diagnostics, OD=20cm
 - Downstream: for hydraulic system piping, OD=20cm
- The direction is optimized to minimize radiation leakage to TT2 tunnel
 - Could be filled with sand bags after the installation of the cables if radiation is an issue



The Experimental Layout





The Experimental Layout



Control Room

- Location to be decided – two options:
 1. At the ISR tunnel at the exit from TT2 tunnel
 - Need to reserve the space from other users
 - Not the ideal place for a control room
 2. Use the old West Area CR in bat.272
 - Further away but at walking distance from the tunnel door
 - Next to the cryogenics lab there the surface tests will be made

- Decisive factor would be the cabling. Are cables installations required between TT2 & CR?
 - Can all communication be based on Ethernet network?

- Aim to conclude on this issue by end of April 2006




Installation Schedule



- Target date: **November 2006!**
 - Ready to receive and install the solenoid and Hg-loop into the tunnel
- Infrastructure in the tunnel has to be finished beforehand
- Installation and commissioning of solenoid and Hg-loop only at the TT2A tunnel
- Working schedule available taking into account:
 - Installation delays: manpower, tendering, ordering, ...
 - Access limitations due to PS/SPS operation in 2006

CERN Code status – March 2006

- Total credited: 700 CHF (560 USD)
- Committed from BNL: 320 kCHF
- Spent to date: 85 kCHF
 - Pipeline : 25 kCHF





Conclusions



- Lot of progress on MERIT installation issues
 - Power supply, DC cabling, TT10 vent line, cable passages, ...
- Experiment layout available with preliminary allocation of the various system components
- Progress on Safety issues
 - ISIEC form and presentation in relevant committees
 - Review of solenoid and cryogenics systems
- Integration schedule on track
 - Tendering & construction of cryogenics DVB on critical path
 - Cryogenics must proceed to schedule
- Our goal remains to have beam at the startup in 2007