

MERIT Hg System Status

V.B. Graves

P.T. Spampinato

T.A. Gabriel

Muon Collaboration Friday Meeting

March 17, 2006




Executive Summary

- Hg system design has been completed
- Syringe pump fabrication is nearly complete
- Drawing packages for remainder of system are either in fabrication or out for bid
 - **Modifications being performed to target module design due to fabrication quotes being above budget**
- System testing at ORNL scheduled to begin in May

Now for some details...




Experiment Layout

- Hg target is a self-contained module inserted into the magnet bore
- Two containment barriers between the Hg and the tunnel environment
- Hydraulic pump will be in adjacent tunnel, personnel in remote control room





Hg Delivery System

- **Primary containment**
 - Hg-wetted components
 - Capacity 23liters Hg (~760 lbs)
 - Jet duration up to 12 sec
- **Secondary containment**
 - Hg leak/vapor containment
 - Ports for instruments, Hg fill/drain, hydraulics
- **Optical diagnostic components**
 - Passive optics
 - Shadow photography
- **Beam Windows**
 - Ti alloy components that directly interact with beam
 - Single windows on primary, double windows on secondary







MERIT Side View




Syringe Status

- Syringe vendor **Airline Hydraulics Corp (AHC)**
 - Bensalem, PA
- AHC provided system design based on functional requirements specification
- System consists of all syringe pump components
- Status
 - Integration of cylinders & control system starting this week
 - System factory acceptance testing March 30





Additional Syringe Work

- Syringe procurement initiated Sept '05 due to anticipated long delivery of cylinders
- Fabrication dwgs for remainder of system not completed at that time
 - Dwg pkg now complete
- Prefer to award to syringe pump vendor
- Being coordinated by BNL Procurement




Beam Windows

- Windows fabricated from Ti6Al4V alloy
- Welded attachments provide more usable space for beam
 - **Currently performing a re-design to mechanically attach windows where possible**
- Single windows for primary containment, double windows for secondary
- Pressurize secondary windows, monitor to detect failure



Current Window Design






Proposed Window Design

2006


Target Module

- **Current design of primary/secondary containment modules inserted into magnet utilizes Ti or Ti alloys**
 - Alleviates issues with welding dissimilar metals
- **Material for 2 spare nozzle assemblies will also be procured**
- **Drawing package currently out for bid**
 - Will be coordinated by Princeton Procurement
 - Procurement direction to be decided on cost/schedule considerations
- **Vendor quotes indicate an all-Ti fabrication is beyond our budget, so drawings being modified for SS target module**
 - **Brazing Ti to SS appears feasible**




Secondary Containment

- SS304L/316L 1/2" bottom plate, 1/4" sides
- SS flexible sleeve
- SS cylindrical sleeve
- Lexan top
- Ports
 - Optical diagnostics
 - Instrumentation
 - Hydraulics
 - Hg drain & fill (without opening secondary)
 - Hg extraction (in event of major leak in primary containment)
 - Passive filtration
- Fabrication of box underway at Princeton





Baseplates

- Multiple baseplates required for transport, assembly, and equipment support
- Primarily fabricated from Al 6061-T6
- Fabrication underway at University of Mississippi




LabView-Based Control System

- Remote control over long distance limited control choices
- LabView on laptop computer was chosen as system controller
 - CompactPCI I/O modules at syringe pump control station
 - Communicates to laptop via EtherNet cable
 - Should allow straightforward integration with other MERIT control systems



Labview hardware

Hg Syringe Control System Development Underway



Mercury Containers/Shipping




- Standard flask is 2.5 liters
- Flask + Hg weighs ~35 kg
- Shipping requirements coordinated by ORNL Transportation Group
- MERIT will require a short (20ft) Sealand container for transport to CERN
 - Ship magnet with Hg system



TTF Operations – Hg Filling

- A peristaltic pump for transferring Hg was successfully tested
 - This is the preferred approach for filling & draining MERIT
 - System designed to fill/drain without opening secondary containment
- Hg handling requires multiple spill/drip precautions and ventilation equipment



Mercury Vapors – Filtering & Monitoring

- **Two vapor monitors to be used**
 - One for secondary volume, one for tunnel environment
 - Will communicate with control system
- **Scavenger portable ventilation system will be used**
 - Can be used as stand-alone system or connected to secondary containment
 - Already procured by Princeton
- **Passive filtration on secondary containment**
 - Sulphur-impregnated charcoal & HEPA filtration






MERIT at MIT and CERN

- **Dialogue with CERN & MIT Safety Engineering Group has begun**
 - Presentation/discussion with CERN in August '05
 - Presentation/discussion with MIT at the October Collaboration Meeting
- **Formal safety reviews and test/operation plans to be presented to MIT and CERN during summer 2006**



Schedule - Major Milestones

- **Target Tests at ORNL May-Jul '06**
 - Integrated with optical diagnostics system
- **Integrated Tests at MIT Aug-Sep '06**
 - Retest Oct '06 if nozzle reconfiguration needed
- **Ship MERIT equipment to CERN Nov-Dec '06**
- **Beam Tests at CERN Apr '07**
 - Retest Jun '07, if needed





Conclusions

- Syringe pump system fabrication nearly complete, integration to begin this week
 - Factory acceptance testing March 30
- Final design details & fabrication dwgs of Hg system have been completed
 - Initial nozzle configuration determined
 - Fabrication is underway on baseplates & secondary containment
 - Sump tank assy pkg should be awarded soon
 - **Target module drawings being revised, should go out for bid by end of March**
- Control system development started, need guidance regarding integration with supervisory experiment control system
- Hg system testing at ORNL will begin as soon as equipment becomes available
 - Water testing followed by Hg