

Targetry Plans and Status

MUTAC Review

FNAL

March 17, 2006





International Scoping Study

Question: Given a "Green Field" what are the most favorable parameters for a proton driver to a Neutrino Factory?

A related question: Liquid or Solid Target

Can a solid target survive a >1MW proton driver beam?

(Nick Simos → Solid Target Studies)

Is a liquid target for a >1MW proton driver technically feasible?

(MERIT target experiment at CERN)

What is the "preferred" proton driver energy?







Achieving Intense Muon Beams

Maximize Pion/Muon Production


- Soft-pion Production
- High Z materials
- High Magnetic Field







Optimizing Soft-pion Production









Process mesons through Cooling

Consider mesons within acceptance of $\epsilon_L = 30\pi$ mm and $\epsilon_L = 150\pi$ mm after cooling




NATIONAL LABORATORY



Use Meson count with KE < 350 MeV as a figure of merit.



Meson KE < 350 MeV at 50m



Mesons/Proton


Mesons/Proton normalized to beam power






NATIONAL LABORATORY

Post-cooling 30π Acceptance






Carbon Target Parameters Search





Carbon Target Optimization



NATIONAL LABORATORY
Set R=1.25cm; tilt angle = 50 mrad; Length=60cm; Z=-40cm




Proton KE Scan with Carbon

Count mesons within acceptance of

 $\epsilon_{\perp} = 30\pi \ mm \ and$

 $\varepsilon_{\rm L} = 150\pi \text{ mm}$

after cooling







Summary of Results

Compare Meson production for Hg at 24 GeV and 10 GeV

$$\frac{N^{+}_{10GeV}}{N^{+}_{24GeV}} = 1.07 \frac{N^{-}_{10GeV}}{N^{-}_{24GeV}} = 1.10$$

Compare Meson production for C at 24 GeV and 5 GeV

$$\frac{N^{+}_{5GeV}}{N^{+}_{24GeV}} = 1.90 \qquad \frac{N^{-}_{5GeV}}{N^{-}_{24GeV}}$$

Compare Meson production for Hg at 10 GeV and C at 5 GeV

$$\frac{N^{+}_{Hg-10GeV}}{N^{+}_{C-5GeV}} = 1.18 \frac{N^{-}_{Hg-10GeV}}{N^{-}_{C-5GeV}} = 1.22$$





The Target Experiment at CERN


"R&D on the muon production target experiment at CERN will also be funded"

Presidential FY07 Budget Request to Congress






The MERIT (nTOF11) Experiment








Target Test Site at CERN







The Tunnel Complex







Profile of the Experiment

- 14 and 24 GeV Proton beam
- Up to $>30 \times 10^{12}$ Protons (TP) per 2µs spill
- Proton beam spot with $r \le 1.5$ mm rms
- 1cm diameter Hg Jet
- Hg Jet/Proton beam off solenoid axis
 - Hg Jet 33 mrad
 - Proton beam 67 mrad
- Test 50 Hz operations
 - 20 m/s Hg Jet
 - 2 spills separated by 20 ms





PS Beam Characteristics

- PS will run in a harmonic 16 mode
- We can fill any of the 16 rf buckets with sub-bunches at our discretion.
- Each microbunch can contain up to 3 TP.
- Fast extraction can accommodate entire 2µs PS fill.
- Extraction at 24 GeV
- Partial/multiple extraction possible at 14 GeV
- Beam on target April 2007





Run plan for PS beam spills

The PS Beam Profile allows for:

- Varying beam charge intensity from 6 TP to > 30 TP.
- Studying influence of solenoid field strength on beam dispersal (vary B₀ from 0 to 15T).
- Study possible cavitation effects by varying PS spill structure (Pump/Probe)
- Study 50 Hz operation.





Key Experimental Sub-systems

15T Pulsed Solenoid

8 MVA Power Supply

LN₂ Cryo-system

Hg Jet Delivery System (K. McDonald)

Diagnostics (K. McDonald)

Optical

Particle Detection


CERN Infrastructure (I. Efthymiopoulos)


Simulations (R. Samulyak)





High Field Pulsed Solenoid





- 80° K Operation
- 15 T with 5.5 MW Pulsed Power
- 15 cm warm bore
- 1 m long beam pipe

Peter Titus, MIT





Pulsed Solenoid Milestones

Delivery to MIT January 06

Reception Testing March 06

Integration Testing September 06

Ship to CERN December 06

Installation at CERN January 07






The Pulsed Solenoid



CVIP December 2005




First Current: MIT March 9, 2006





System Commissioning

- Ship Pulsed Solenoid to MIT January 2006
- Test Solenoid to 15 T peak field March-April 2006
- Integration of Solenoid/Hg Jet system September 2006







Power Supply Milestones

Site Preparations January 06

Relocate and Install February 06

DC Cabling March 06

AC Cabling March 06

Refurbish PS March-April 06

Interlocks September 06

Commissioning October 06





Power Converter (From SPPS Transfer Line)

8000 Adc, 1000 Vdc

Strategy:

• Refurbishment of the West Area Power Converter, making it compatible with the project requirements

Passive filter

Global view



Rectifier bridges





Passive filter capacitors







Cryogenic System Milestones

TT10 Vent Installation

Cold Valve Box Fabrication

Control System Development

Surface Preparations

Transfer Line Installation

Cold Valve Box Testing

Heater System Installation

Cold Valve Box Installation

Commissioning

January 06

April-July 06

January-June 06

May 06

July 06

October 06

September 06

November 06

December 06






The Cryogenic System

Key Features

- •30 minutes rep-rate
- •LN₂ purge before shot
- •Liquid purge to buffer storage
- •Gas purge to TT10







Cryosytem Layout

LN₂ and N₂ gas stored on the surface.


Cold valve box in the TT2 tunnel.

Exhaust gas vented into TT10 tunnel through filtration system.

~ 150 liters of LN₂ per Magnet pulse.

Magnet flushed with N₂ prior to each pulse, to minimize activation of N₂.






Harold G. Kirk




The Cold Valve Box (DVB)







The Hg Jet System








The Hg Jet Injection System


Z = 0 at the Solenoid midpoint. The Hg Jet axis and proton beam trajectory intersect.








Primary Containment Cross Section





Princeton Nozzle R&D







The Nozzle Test Setup





Fast camera capture of waterjet September 16, 2005 @ Princeton





Measured Waterjet Velocity 12 m/s

nozzle: diameter ~8 mm, length 6-inch

Camera: FastVision 13 capability 1280x1024 pixels, 500 frames/sec, 0.5 sec video





Project Major Sub-systems

| | 2005 | 2006 | 2006 | 2006 | 2006 | 2007 |
|---------------------|------|------|------|------|------|------|
| | Q4 | Q1 | Q2 | Q3 | Q4 | Q1 |
| Magnet | | | | | | |
| Magnet Delivery | | | | | | |
| Receiving Testing | | | | | | |
| Integration Testing | | | | | | |
| Shipping | | | | | | |
| Installation | | | | | | |
| Hg Jet | | | | | | |
| System Fabrication | | | | | | |
| Nozzle Development | | | | | | |
| Optical Diagnostics | | | | | | |
| System Testing ORNL | | | | | | |
| System Testing MIT | | | | | | |
| Shipping | | | | | | |
| Installation | | | | | | |



CERN Infrastructure

| | 2005 | 2006 | 2006 | 2006 | 2006 | 2007 |
|----------------------|------|------|------|------|------|------|
| | Q4 | Q1 | Q2 | Q3 | Q4 | Q1 |
| Power Supply | | | | | | |
| Site Preparations | | | | | | |
| Installation | | | | | | |
| DC Cabling | | | | | | |
| AC Cabling | | | | | | |
| Interlocks | | | | | | |
| Commissioning | | | | | | |
| Cryogenics | | | | | | |
| TT10 Vent | | | | | | |
| Cold Valve Box Fab. | | | | | | |
| System Testing CERN | | | | | | |
| Surface Preparations | | | | | | |
| Tunnel Installations | | | | | | |
| Commissioning | | | | | | |



Summary

The MERIT (nTOF11) Experiment

- Study single beam pulses with intensities >30TP
- Study influence of solenoid field strength on Hg jet dispersal (B_o from 0 to 15T)
- Study 50 Hz operations scenario
- Study cavitation effects in the Hg jet by varying PS spill structure—Pump/Probe
- First beam expected April 2007
- Confirm Neutrino Factory targetry concept

