

An R&D Program for Targetry and Capture at a Muon Collider Source

K.T. McDonald

Princeton U.

Dec. 10, 1998

Targetry Meeting at Fermilab

<http://puhep1.princeton.edu/mumu/target/>

An R&D Program for Targetry and Capture at a Muon Collider Source

A PROPOSAL TO THE BNL AGS DIVISION

Audrey Bernadon,^d David Brashears,ⁱ Kevin Brown,^b Daniel Carminati,^d
Michael Cates,ⁱ John Corlett,^g F Debray,^f Adrian Fabich,^d Richard C. Fernow,^b
Charles Finfrock,^b Yasuo Fukui,^c Tony A. Gabriel,ⁱ Juan C. Gallardo,^b
Michael A. Green,^g George A. Greene,^b John R. Haines,ⁱ Jerry Hastings,^b
Ahmed Hassanein,^a Michael Iarocci,^b Colin Johnson,^d Stephen A. Kahn,^b
Bruce J. King,^b Harold G. Kirk,^{b,1} Jacques Lettry,^d Vincent LoDestro,^b
Changguo Lu,^j Kirk T. McDonald,^{j,2} Nikolai V. Mokhov,^e
Alfred Moretti,^e James H. Norem,^a Robert B. Palmer,^b Ralf Prigl,^b Helge Ravn,^d
Bernard Riemer,ⁱ James Rose,^b Thomas Roser,^b Roman Samulyak,^b
Joseph Scaduto,^b Peter Sievers,^d Nicholas Simos,^b Philip Spampinato,ⁱ
Iuliu Stumer,^b Peter Thieberger,^b James Tsai,ⁱ Thomas Tsang,^b Haipeng Wang,^b
Robert Weggel,^b Albert F. Zeller,^h Yongxiang Zhao^b

^aArgonne National Laboratory, Argonne, IL 60439

^bBrookhaven National Laboratory, Upton, NY 11973

^cUniversity of California, Los Angeles, CA 90095

^dCERN, 1211 Geneva, Switzerland

^eFermi National Laboratory, Batavia, IL 60510

^fGrenoble High Magnetic Field Laboratory, 38042 Grenoble, France

^gLawrence Berkeley National Laboratory, Berkeley, CA 94720

^hMichigan State University, East Lansing, MI 48824


ⁱOak Ridge National Laboratory, Oak Ridge, TN 37831

^jPrinceton University, Princeton, NJ 08544

(Submitted Sept. 28, 1998)

¹Project Manager. Email: hkirk@bnl.gov


²Spokesperson. Email: kirkmcd@princeton.edu



Targetry Challenges

To achieve useful physics luminosity, a muon collider must produce about 10^{14} μ /sec.

- $> 10^{15}$ proton/sec onto a high- Z target \Leftrightarrow 4 MW beam power.
- Capture pions of $P_{\perp} \lesssim 200$ MeV/ c in a 20-T solenoid magnet.
- Transfer the pions into a 1.25-T-solenoid decay channel.
- Compress π/μ bunch energy with rf cavities and deliver to muon cooling channel.



Issues:

- 400 kW deposited in target.

⇒ Move target material away from beam and cool remotely.

A **free liquid metal jet** is presently the preferred option.

- First rf cavity should be ≈ 3 m from target.

Will it work?

Need a **Targetry R&D Program.**

ISOLDE Liquid Targets Damaged by Short Pulses



Cracks developed at braised joints and lead sprayed out.

R&D Goals

Long Term: Provide a facility to test key components of the front-end of a muon collider in realistic beam conditions.

Near Term (1-2 years): Explore viability of a liquid metal jet target in intense, short proton pulses and (separately) in strong magnetic fields.



(Change target technology if encounter severe difficulties.)

Mid Term (3-4 years): Add 20-T magnet to AGS beam tests; Test 70-MHz rf cavity (+ 1.25-T magnet) downstream of target; Characterize pion yield.

The 8 Steps in the R&D Program




1. Simple tests of liquid (Ga-Sn) targets in the AGS FEB U-line.
2. Test of liquid jet entering a 20-T magnet (20-MW cw Bitter magnet at the National High Field Magnet Laboratory).
3. Test of liquid jet in the FEB U-line (without magnet).
4. Add 20-T pulsed magnet (4-MW peak) to the FEB U-line.
5. Add 70-MHz rf cavity downstream of target in FEB U-line.
6. Surround rf cavity with 1.25-T magnet.
7. Characterize pion yield from target + magnet system in FEB U-line.
8. Ongoing simulation of the thermal hydraulics of the liquid-metal target system.

Test Beam: AGS FEB U-Line



Immediate Goal: Upgrade FEB U-Line for Smaller Spot Size and Greater Intensity

-- uf730 Wed Nov 18 06:42:53 1998 --
Framegrabber = seb-fg1
Signal Range = 0 157
Centroid = 7.07032 3.39971 mm
Center = 2.58813 -0.144885 mm
Sigma = 4.01048 10.8851 mm
!!Failed 2D Gauss Fit!!
Intensity = 1152191
Attenuation = 0%




Begin with Ga/Sn Liquid-Metal Alloy

Eutectic Ga/Sn alloy melts at 20C. Density = 6 g/cm³.






Easy to make and handle; very low viscosity.



Build pulsed jet following design of C. Johnson:




Fiberoptic Strain Sensors




First Test: Liquid Metal in a Trough, a Pipe and Free Flow

TOP VIEW



CAMERA VIEW



Institutional Involvement

Topic	Institutions
1. Initial Tests	BNL, CERN, ORNL, Princeton
2. Liquid jet + 20-T magnet	BNL, Princeton , NHMFL
3. Full-scale jet, 10^{14} ppp	ANL, BNL , CERN, Princeton
4. Full-scale jet + pulsed 20-T magnet	ANL, BNL , CERN, Princeton
5. RF cavity + short beam pulse	BNL , CERN, Fermilab, LBL, Princeton
6. RF cavity + 1.25-T magnet	BNL , LBL, Princeton
7. Pion-production measurement	BNL , Fermilab, LBL, Princeton
8. Simulation + exploding wire tests	ANL , BNL, Fermilab, ORNL, Princeton

Targetry R&D Budget

FY 99

Task	ANL	BNL	Princeton	Total
Initial Jet Studies		85	85	170
AGS Beamline Upgrades		100		100
Pulsed Solenoid Design		50		50
RF Systems		100		100
Simulation Studies	75		5	80
Total	75	335	90	\$500k

Appendices:

ID	Task Name	Duration	Cost	Start	Finish	1Q99	2Q99	3Q99	4Q99	1Q00	2Q00	3Q00	4Q00	1Q01	2Q01	3Q01	4Q01	1Q02	2Q02	3Q02	4Q02					
1	Targetry R&D	1040 days	\$7,110,000	Fri 1/1/99	Thu 12/26/02	[Gantt bar]																				
2	Liquid Metal I	100 days	\$130,000	Fri 1/1/99	Thu 5/20/99	[Gantt bar]																				
3	Initial Beam Test	55 days	\$80,000	Fri 1/1/99	Thu 3/18/99	[Gantt bar]																				
4	Containment Vessel	30 days	\$30,000	Fri 1/1/99	Thu 2/11/99	[Gantt bar]																				
5	Instrumentation	45 days	\$40,000	Fri 1/1/99	Thu 3/4/99	[Gantt bar]																				
6	Test at AGS, I	10 days	\$10,000	Fri 3/5/99	Thu 3/18/99	[Gantt bar]																				
7	3 mm Jet Test	100 days	\$50,000	Fri 1/1/99	Thu 5/20/99	[Gantt bar]																				
8	Jet fabricaton	90 days	\$20,000	Fri 1/1/99	Thu 5/6/99	[Gantt bar]																				
9	Containment Vessel	20 days	\$10,000	Tue 2/9/99	Mon 3/8/99	[Gantt bar]																				
10	Instrumentation	20 days	\$10,000	Tue 3/9/99	Mon 4/5/99	[Gantt bar]																				
11	Test at AGS, II	10 days	\$10,000	Fri 5/7/99	Thu 5/20/99	[Gantt bar]																				
12	Jet Test at FSU Magnet	50 days	\$60,000	Mon 4/5/99	Fri 6/11/99	[Gantt bar]																				
13	Containment Vessel	20 days	\$20,000	Mon 4/5/99	Fri 4/30/99	[Gantt bar]																				
14	Instrumentation	20 days	\$20,000	Mon 5/3/99	Fri 5/28/99	[Gantt bar]																				
15	Test at FSU	10 days	\$20,000	Mon 5/31/99	Fri 6/11/99	[Gantt bar]																				
16	2 cm Jet, 1e14 p's	530 days	\$600,000	Fri 1/1/99	Thu 1/11/01	[Gantt bar]																				
17	2 cm Jet	100 days	\$90,000	Mon 5/3/99	Fri 9/17/99	[Gantt bar]																				
18	Design	60 days	\$20,000	Mon 5/3/99	Fri 7/23/99	[Gantt bar]																				
19	Jet Fabrication	45 days	\$20,000	Mon 6/28/99	Fri 8/27/99	[Gantt bar]																				
20	Containment Vessel	30 days	\$20,000	Mon 7/26/99	Fri 9/3/99	[Gantt bar]																				
21	Instrumentation	20 days	\$20,000	Mon 7/26/99	Fri 8/20/99	[Gantt bar]																				
22	Test at AGS, III	10 days	\$10,000	Mon 9/6/99	Fri 9/17/99	[Gantt bar]																				
23	1e14 ppp	530 days	\$510,000	Fri 1/1/99	Thu 1/11/01	[Gantt bar]																				
24	AGS Extraction Upgr.	520 days	\$500,000	Fri 1/1/99	Thu 12/28/00	[Gantt bar]																				
25	Test at AGS, IV	10 days	\$10,000	Fri 12/29/00	Thu 1/11/01	[Gantt bar]																				
26	Pulsed Solenoid	550 days	\$1,020,000	Fri 10/1/99	Thu 11/8/01	[Gantt bar]																				
27	Design	200 days	\$100,000	Fri 10/1/99	Thu 7/6/00	[Gantt bar]																				
28	Coil Purchase/Fabrication	250 days	\$500,000	Fri 7/7/00	Thu 6/21/01	[Gantt bar]																				
29	Commisioning	60 days	\$100,000	Fri 6/22/01	Thu 9/13/01	[Gantt bar]																				
30	LN2 Cryostat Design	7 days	\$50,000	Fri 7/7/00	Mon 7/17/00	[Gantt bar]																				
31	LN2 Cryostat Fabrication	50 days	\$100,000	Tue 7/18/00	Mon 9/25/00	[Gantt bar]																				
32	LN2 Handling	40 days	\$20,000	Tue 9/26/00	Mon 11/20/00	[Gantt bar]																				
33	Move/Refurbish PS	40 days	\$40,000	Wed 10/4/00	Tue 11/28/00	[Gantt bar]																				
34	Move Substation	40 days	\$40,000	Wed 11/29/00	Tue 1/23/01	[Gantt bar]																				
35	Substation Attachment	20 days	\$20,000	Wed 1/24/01	Tue 2/20/01	[Gantt bar]																				
36	Switching System	45 days	\$30,000	Wed 2/21/01	Tue 4/24/01	[Gantt bar]																				
37	Test at AGS, V	40 days	\$20,000	Fri 9/14/01	Thu 11/8/01	[Gantt bar]																				
38	RF Systems	680 days	\$1,650,000	Fri 10/1/99	Thu 5/9/02	[Gantt bar]																				
39	RF Cavity	680 days	\$950,000	Fri 10/1/99	Thu 5/9/02	[Gantt bar]																				
40	Design	260 days	\$120,000	Fri 10/1/99	Thu 9/28/00	[Gantt bar]																				
41	Purchase/Fabricate	260 days	\$600,000	Fri 9/29/00	Thu 9/27/01	[Gantt bar]																				
42	Assembly	20 days	\$20,000	Fri 9/28/01	Thu 10/25/01	[Gantt bar]																				
43	Testing w/o beam	60 days	\$30,000	Fri 10/26/01	Thu 1/17/02	[Gantt bar]																				
44	Refurbish/rebuild	20 days	\$150,000	Fri 1/18/02	Thu 2/14/02	[Gantt bar]																				
45	Test at AGS, VI	60 days	\$30,000	Fri 2/15/02	Thu 5/9/02	[Gantt bar]																				
46	Site Preparation	254 days	\$300,000	Tue 8/1/00	Fri 7/20/01	[Gantt bar]																				
47	Design	30 days	\$30,000	Tue 8/1/00	Mon 9/11/00	[Gantt bar]																				
48	Blockhouse	60 days	\$150,000	Tue 9/12/00	Mon 12/4/00	[Gantt bar]																				
49	Shielding	60 days	\$30,000	Tue 12/5/00	Mon 2/26/01	[Gantt bar]																				
50	Power Service	70 days	\$20,000	Wed 2/28/01	Tue 6/5/01	[Gantt bar]																				
51	Vacuum	120 days	\$50,000	Mon 2/5/01	Fri 7/20/01	[Gantt bar]																				
52	DI Water	45 days	\$20,000	Tue 5/1/01	Mon 7/2/01	[Gantt bar]																				
53	LBL Transfer	50 days	\$50,000	Fri 10/1/99	Thu 12/9/99	[Gantt bar]																				
54	Testing	40 days	\$40,000	Fri 10/1/99	Thu 11/25/99	[Gantt bar]																				
55	Packing	5 days	\$5,000	Fri 11/26/99	Thu 12/2/99	[Gantt bar]																				
56	Shipping	5 days	\$5,000	Fri 12/3/99	Thu 12/9/99	[Gantt bar]																				
57	Low Level RF	105 days	\$40,000	Wed 4/5/00	Tue 8/29/00	[Gantt bar]																				

ID	Task Name	Duration	Cost	Start	Finish	1Q99	2Q99	3Q99	4Q99	1Q00	2Q00	3Q00	4Q00	1Q01	2Q01	3Q01	4Q01	1Q02	2Q02	3Q02	4Q02	
58	Design	30 days	\$10,000	Wed 4/5/00	Tue 5/16/00																	
59	Procurement	45 days	\$20,000	Wed 5/17/00	Tue 7/18/00																	
60	Testing	30 days	\$10,000	Wed 7/19/00	Tue 8/29/00																	
61	Pulsing System	200 days	\$110,000	Thu 8/3/00	Wed 5/9/01																	
62	Design	60 days	\$30,000	Thu 8/3/00	Wed 10/25/00																	
63	Procurement	60 days	\$30,000	Thu 10/26/00	Wed 1/17/01																	
64	Crowbar	60 days	\$30,000	Thu 1/18/01	Wed 4/11/01																	
65	Testing	20 days	\$20,000	Thu 4/12/01	Wed 5/9/01																	
66	Power Combiner	150 days	\$200,000	Wed 1/3/01	Tue 7/31/01																	
67	Design	60 days	\$80,000	Wed 1/3/01	Tue 3/27/01																	
68	Procurement	60 days	\$100,000	Wed 3/28/01	Tue 6/19/01																	
69	Testing	30 days	\$20,000	Wed 6/20/01	Tue 7/31/01																	
70	RF Solenoid	529 days	\$1,110,000	Mon 8/7/00	Thu 8/15/02																	
71	Coil Design	120 days	\$60,000	Mon 8/7/00	Fri 1/19/01																	
72	Coil Fabricate	300 days	\$500,000	Mon 1/22/01	Fri 3/15/02																	
73	Iron Design	120 days	\$60,000	Mon 1/22/01	Fri 7/6/01																	
74	Iron Fabricate	150 days	\$200,000	Mon 7/9/01	Fri 2/1/02																	
75	Support Design	80 days	\$40,000	Mon 7/9/01	Fri 10/26/01																	
76	Support Fabricate	100 days	\$50,000	Mon 10/29/01	Fri 3/15/02																	
77	Block House	80 days	\$20,000	Mon 6/4/01	Fri 9/21/01																	
78	Move/Refurbish PS	60 days	\$30,000	Mon 9/24/01	Fri 12/14/01																	
79	Substation Attachment	20 days	\$20,000	Mon 12/17/01	Fri 1/11/02																	
80	Commsioning	60 days	\$120,000	Fri 5/10/02	Thu 8/1/02																	
81	Test at AGS, VII	10 days	\$10,000	Fri 8/2/02	Thu 8/15/02																	
82	Capture Experiment	634 days	\$1,770,000	Mon 7/3/00	Thu 12/5/02																	
83	Bent Solenoid Design	60 days	\$30,000	Tue 2/6/01	Mon 4/30/01																	
84	Bent Solenoid Fabrication	300 days	\$500,000	Tue 5/1/01	Mon 6/24/02																	
85	Guide Dipole Design	30 days	\$20,000	Tue 5/1/01	Mon 6/11/01																	
86	Guide Dipole Fabrication	180 days	\$150,000	Tue 6/12/01	Mon 2/18/02																	
87	Transition Magnet Design	30 days	\$20,000	Tue 6/12/01	Mon 7/23/01																	
88	Transition Magnet fabricat	120 days	\$100,000	Tue 7/24/01	Mon 1/7/02																	
89	Power Supplies	90 days	\$100,000	Wed 1/2/02	Tue 5/7/02																	
90	TPC system	500 days	\$240,000	Wed 7/5/00	Tue 6/4/02																	
91	TOF System	500 days	\$120,000	Wed 7/5/00	Tue 6/4/02																	
92	PWCs and scintillators	500 days	\$150,000	Mon 7/3/00	Fri 5/31/02																	
93	Electronics and DAQData	500 days	\$200,000	Tue 7/4/00	Mon 6/3/02																	
94	Counting Trailer	60 days	\$60,000	Thu 1/3/02	Wed 3/27/02																	
95	Commsioning	50 days	\$50,000	Fri 8/16/02	Thu 10/24/02																	
96	Test at AGS, VIII	30 days	\$30,000	Fri 10/25/02	Thu 12/5/02																	
97	Simulation & Validation	1040 days	\$770,000	Fri 1/1/99	Thu 12/26/02																	
98	Simulation	1040 days	\$600,000	Fri 1/1/99	Thu 12/26/02																	
99	Exploding Wire I	200 days	\$110,000	Mon 1/3/00	Fri 10/6/00																	
100	Capacitor Bank	120 days	\$60,000	Mon 1/3/00	Fri 6/16/00																	
101	Test Cell, Water	20 days	\$10,000	Mon 6/19/00	Fri 7/14/00																	
102	Instrumentation	30 days	\$30,000	Mon 7/17/00	Fri 8/25/00																	
103	Data Collection	30 days	\$10,000	Mon 8/28/00	Fri 10/6/00																	
104	Exploding Wire II	210 days	\$40,000	Mon 10/9/00	Fri 7/27/01																	
105	Test Cell, Liquid Met	30 days	\$10,000	Mon 10/9/00	Fri 11/17/00																	
106	Data Collection	180 days	\$30,000	Mon 11/20/00	Fri 7/27/01																	
107	Exploding Wire III	60 days	\$20,000	Wed 10/3/01	Tue 12/25/01																	
108	Test Cell in Magnet	30 days	\$10,000	Wed 10/3/01	Tue 11/13/01																	
109	Data Collection	30 days	\$10,000	Wed 11/14/01	Tue 12/25/01																	

	1999	2000	2001	2002	Total
Targetry R&D					
Liquid Metal I					
Initial Beam Test					
Containment Vessel	\$30,000				\$30,000
Instrumentation	\$40,000				\$40,000
Test at AGS, I	\$10,000				\$10,000
3 mm Jet Test					
Jet fabrication	\$20,000				\$20,000
Containment Vessel	\$10,000				\$10,000
Instrumentation	\$10,000				\$10,000
Test at AGS, II	\$10,000				\$10,000
Jet Test at FSU Magnet					
Containment Vessel	\$20,000				\$20,000
Instrumentation	\$20,000				\$20,000
Test at FSU	\$20,000				\$20,000
2 cm Jet, 1e14 p's					
2 cm Jet					
Design	\$20,000				\$20,000
Jet Fabrication	\$20,000				\$20,000
Containment Vessel	\$20,000				\$20,000
Instrumentation	\$20,000				\$20,000
Test at AGS, III	\$10,000				\$10,000
1e14 ppp					
AGS Extraction Upgrade	\$250,962	\$249,039			\$500,000
Test at AGS, IV		\$1,000	\$9,000		\$10,000
Pulsed Solenoid					
Design	\$33,000	\$67,000			\$100,000
Coil Purchase/Fabrication		\$252,000	\$248,000		\$500,000
Commissioning			\$100,000		\$100,000
LN2 Cryostat Design		\$50,000			\$50,000
LN2 Cryostat Fabrication		\$100,000			\$100,000
LN2 Handling		\$20,000			\$20,000
Move/Refurbish PS		\$40,000			\$40,000
Move Substation		\$23,000	\$17,000		\$40,000
Substation Attachment			\$20,000		\$20,000
Switching System			\$30,000		\$30,000
Test at AGS, V			\$20,000		\$20,000
RF Systems					
RF Cavity					
Design	\$30,462	\$89,539			\$120,000
Purchase/Fabricate		\$152,308	\$447,692		\$600,000
Assembly			\$20,000		\$20,000
Testing w/o beam			\$23,500	\$6,500	\$30,000
Refurbish/rebuild				\$150,000	\$150,000
Test at AGS, VI				\$30,000	\$30,000
Site Preparation					
Design		\$30,000			\$30,000
Blockhouse		\$150,000			\$150,000
Shielding		\$9,500	\$20,500		\$30,000
Power Service			\$20,000		\$20,000
Vacuum			\$50,000		\$50,000
DI Water			\$20,000		\$20,000
LBL Transfer					
Testing	\$40,000				\$40,000
Packing	\$5,000				\$5,000
Shipping	\$5,000				\$5,000
Low Level RF					
Design		\$10,000			\$10,000
Procurement		\$20,000			\$20,000
Testing		\$10,000			\$10,000
Pulsing System					
Design		\$30,000			\$30,000
Procurement		\$77,125	(\$47,125)		\$30,000
Crowbar			\$30,000		\$30,000
Testing			\$20,000		\$20,000
Power Combiner					
Design			\$80,000		\$80,000
Procurement			\$100,000		\$100,000
Testing			\$20,000		\$20,000
RF Solenoid					
Coil Design		\$52,500	\$7,500		\$60,000
Coil Fabricate			\$410,000	\$90,000	\$500,000
Iron Design			\$60,000		\$60,000
Iron Fabricate			\$168,000	\$32,000	\$200,000
Support Design			\$40,000		\$40,000
Support Fabricate			\$23,000	\$27,000	\$50,000
Block House			\$20,000		\$20,000
Move/Refurbish PS			\$30,000		\$30,000
Substation Attachment			\$11,000	\$9,000	\$20,000
Commissioning				\$120,000	\$120,000
Test at AGS, VII				\$10,000	\$10,000
Capture Experiment					
Bent Solenoid Design			\$30,000		\$30,000
Bent Solenoid Fabrication			\$291,667	\$208,333	\$500,000
Guide Dipole Design			\$20,000		\$20,000
Guide Dipole Fabrication			\$120,833	\$29,167	\$150,000
Transition Magnet Design			\$20,000		\$20,000
Transition Magnet fabrication			\$95,833	\$4,167	\$100,000
Power Suplies				\$100,000	\$100,000
TPC system		\$61,440	\$125,280	\$53,280	\$240,000
TOF System		\$30,720	\$62,640	\$26,640	\$120,000
PWCs and scintillators		\$39,000	\$78,300	\$32,700	\$150,000
Electronics and DAQData acquisition		\$200,000			\$200,000
Counting Trailer				\$60,000	\$60,000
Comissioning				\$50,000	\$50,000
Test at AGS, VIII				\$30,000	\$30,000
Simulation & Validation					
Simulation	\$150,577	\$150,000	\$150,577	\$148,848	\$600,000
Exploding Wire I					
Capacitor Bank		\$60,000			\$60,000
Test Cell, Water		\$10,000			\$10,000
Instrumentation		\$30,000			\$30,000
Data Collection		\$10,000			\$10,000
Exploding Wire II					
Test Cell, Liquid Metal		\$10,000			\$10,000
Data Collection		\$5,000	\$25,000		\$30,000
Exploding Wire III					
Test Cell in Magnet			\$10,000		\$10,000
Data Collection			\$10,000		\$10,000
Total	\$795,000	\$2,039,170	\$3,058,198	\$1,217,633	\$7,110,000